

United India Insurance Company Limited

Proposed Renovation & Interior work for Residence

Flat No. 802, 8th Floor, Amidhara Apartment, Opp. Sarjan Society

Name of the Bidder				
Items	Particular of items of Works	Quantity	Units	Rate
Sr. No.				Rs. Ps.
1	Proposed vitrified flooring on the existing flooring with proper chemical adhesive in all rooms	320	Sq. Ft.	
	Bed Rooms & Passage.			
2	Marble floor polishing in Living room @ 210.00 Sq. Ft.	1	Unit	
3	Kota stone polishing in Kitchen & Kitchen platform & chokedi	102	Sq. Ft.	
4	Glazed tiles dado, for Flooring & Wall in Toilet ,W. C. & Bathroom	353	Sq. Ft.	
5	Kota stone Kitchen platform	1	Unit	
	wall glazed tiles cleaning & repairing.@ 27.00 Sq. Ft.			
6	Shutter below kitchen platform	1	Unit	
	Total kitchen platform length ' with all the fittings. As per opening @ 15 Sq. Ft.			

7	Cement re-plastering, removing the old plastering in toilet, Bathroom wall @ 71.00 Sq. Ft.	1	Unit	
	W. C. Ceiling plaster @ 11.00 Sq. Ft.			
8	Black Granite stone Doors Framing, Approved Brand P. V. C. Doors New Doors. for Bathroom, W. C., kitchen, Toilet & Vents	4	Nos.	
	Doors=2'-6" x 7'. 0"= 83.00 Sq. Ft. , Total 4 Nos.			
9	New Doors/windows frame and shutters in Bed room @ 22.60 Sq. Ft.	1	Unit	
10	Front door refitting & Repairing. changing the accessories.	1	Unit	
11	Existing Windows repairing, Removing the existing grill & inserting the S. S. round bars	4	No.	
	No. of windows total 04.			
12	Color Wash in the entire building inside & partly passage Portion.			
	& painting of the existing doors & windows. Remove all the old color wok and painting work and provide new one as per			
	1)Color work inside the rooms	2972	Sq. Ft.	

	2)Color work o/s the building / passage/Ducts , Doors & windows Both side	1	Unit	
13	Living room wooden folded door re fitting 2.00 x2.10 = 4.2 = 45.20 Sq. Ft.	1	Unit	
14	Balcony Grill Refitting & Repairing	3	Nos.	
	K. B., B.B -1, B. B. -2 @ 65.00 Sq. Ft.			
15	Removing all the electric work in the building & proving the new all the lines as per schedule & Electrical Accessory.	1	Unit	
16	Plumbing work with all I.S.I. mark Fittings as per schedule 11 Items with new Water supply lines & Drainage Lines as per the present location, with necessary fittings etc. complete.	1	Unit	
17	Removal of all the debris & cleaning entire the building. From 5th Floor to	1	Unit	
	G. F. & dispose off as per the municipal Direction.			
18	New Unreported work on the site while working.			
Total Amount(Rs)				

Lighting Schedule

Light Points for the area	Ceiling light Point	Wall Bracket Light Point	Fan Point/ Regulator	Plug Point
	1	2	3	4
902				
Entrance Verandah	1			
Living room	2	2	2	2
L- Balcony	1			
Kitchen	1	1	1	2
K- Balcony	1			
Passage	1			1
W. C./ Vent	1			
Bathroom	1			
Bed room -01		1	1	1
Bed Balcony				
Bed Room-02		1	1	1
Toilet -02		1		1
B -2 Balcony	1			

Items	Particular of items of Works	Quantity	Units	Rate
-------	------------------------------	----------	-------	------

Sr. No.	WORKS			Rs. Ps.
1	Light Points: Ceiling, Wall, Fan, Socket, 05 Amps point Etc.	40	Nos.	
2	15 Amps point/ A. C.	2	Nos.	
3	M. C. B. switches fittings	3	Nos.	
4	Main Switch : Two T. P. N. @ Rs. 700/- Three T. P. N. @ Rs. 1700/- R. C. C. B. 40 Amps. Four Pole M. C. B. @ Rs. 2800/- Synder, C & S Make.	1	Nos.	
5	Accessories Tube Light Fan Bulb Vent Fan Geyser R. O.	 5 5 10 2 2 1	 Nos. Nos. Nos. Nos. Nos. Nos.	
6	A. C. cable from G. F. to Flat 4 MM Square: 9+2=11 x3=33Mts.	33	Mts.	
7	Per room Rs. 2000/- for Main Line	1	Unit	
8	R. C. C. B.	1	Unit	
9	Total			
10	Removing all old lines, disposal of waste materials, Expenses for Material Lifting From G. F. to flat , etc.	1	Unit	
Total Amount(Rs)				

Plumbing Schedule Water supply & Drainage

	dian/ opean / 1 / floor	Tap	flush	ower
--	-------------------------------	-----	-------	------

	In Eur wal		F	Sl
W. C.	I	1	1	
Bath		1		1
Passage				
Kitchen Platform		1+1		
Toilet-1	1	2	1	1

Items	Particular of items of Works	Quantity	Units	Rate
Sr. No.				Rs. Ps.
1	Indian or European Pan As per Requirement	2	Nos.	
2	Bib cock/Tap	6	Nos.	
3	Flush	2	Nos.	
4	Shower	2	Nos.	
5	Wash Basin-Set	2	Nos.	
6	Mirror	2	Nos.	
7	Towel Stand	3	Nos.	
8	Mixer for hot & cold water	2	Nos.	
9	Gezer	2	Nos.	
10	Piping water supply & Drainage	1	Unit	
Total Amount(Rs)				

5 AMP Plug Point	15 AMP plug Point/A. C.	M C B Switch	Switch Board	Main Switch	Main Fuse (Supply board) BBoard	Door Bell point
5	6	7	8	9	10	11
		1	1	1	1	
			2			1
1			2			
			1			
			1			
			1			
			1			

Per	Amount
-----	--------

Gezer/R. O.	Two way Switches	Vent Fan	Fan	Tube light	Bulb @ 15 Watt		Total
12	13	14	15	16	17	18	19
	1				1		
	1		2	2	2		
					1		
1			1	1	1		
					1		
					1		
					1		
					1		
			1	1	1		
			1	1	1		

--	--	--	--	--	--	--

[illegible]