

SCHEDULE FOR AIR-CONDITIONING WORK AT UNITED INDIA INSURANCE COMPANY , THRISSUR						
SL.NO	DESCRIPTION	UNIT	QTY	RATE	RATE IN WORDS	AMOUNT
A	<u>MACHINE SIDE</u>					
1	HIGHWALL SPLIT UNITS (5 Star - Inverter type)					
	Supply of Air Cooled Split type Air Conditioners comprising High wall split Indoor Units ,R32 Gas, Outdoor Condensing unit (with copper coil) , isolating valves, thermostatic control, safety cutouts, Power connections, Operating on 230Volts / 50 Hz, Single Phase Supply , vibration isolation pads and Cordless remote control.					
	MAKE - BLUESTAR/DAIKIN/MISTUBHUSHI					
1.1	2 TR Split Units	NOS	5			
1.2	1.0 TR Split Units	NOS	4			
	Total					
	Total value for Machine side (without GST) -A					
B	<u>LOW SIDE WORKS</u>					
2	HIGHWALL SPLIT UNITS (5 Star - Inverter type)					
	Installation Testing & commissioning of Air Cooled Split type Air Conditioners comprising High wall split Indoor Units ,R32 Gas, Outdoor Condensing unit (with copper coil) , isolating valves, thermostatic control, safety cutouts, Power connections, Operating on 230Volts / 50 Hz, Single Phase Supply , vibration isolation pads and Cordless remote control.					
	MAKE - BLUESTAR					
2.1	2 TR Split Units	NOS	5			
2.2	1.0 TR Split Units	NOS	4			
3	<u>REFRIGERANT PIPING</u>					
	Supply Installation and Commissioning of hard/soft copper Refrigerant piping, complete with fittings, elbows, bends, supporting arrangement on walls (RMT:Suction & Discharge)					
3.3	1 TR,1.5TR , 2 TR Split Units	RMT	15			
4	<u>STABILIZER</u>					
	Supply and installation of Voltage stabilizer for split units. make- V Guard					
4.1	4 KVA	NOS	3			
4.2	5 KVA	NOS	3			

SCHEDULE FOR AIR-CONDITIONING WORK AT UNITED INDIA INSURANCE COMPANY , THRISSUR						
SL.NO	DESCRIPTION	UNIT	QTY	RATE	RATE IN WORDS	AMOUNT
5	CONTROL CABLING					
5.1	Supply & Installation of 2 Core PVC Insulated flexible control cable with saddles / supportes and PVC conduits to connect outdoor unit with Indoor unit	RMT	15			
6	POWER CABLING					
6.1	Supply & Installation of power cable to connect outdoor unit to isolator	RMT	15			
7	DRAIN LINE					
7.1	Supply & Installation of insulated PVC drain pipe of 25mm dia	RMT	15			
8	OUTDOOR STAND					
8.2	Supply & Installation of wall mounted support for ODU of split AC	NOS	2			
9	Removal and reinstalling labour for existing 2TR AC with all necessary arrangements	NOS	2			
	TOTAL					
	Total value for Low side work (without GST) - B					
	GRAND TOTAL (A+B)					